

KING COUNTY SECURE COMMUNITY TRANSITION FACILITY

- 2 EXECUTIVE SUMMARY
- 3 OBJECTIVES
- 4 PROJECT APPROACH & STANDARDS
- 5 ABBREVIATIONS & GLOSSARY
- 6 SEQUENCING & RECOMMENDATIONS
- 7 EXISTING COMMUNICATIONS INFRASTRUCTURE
- 9 TELECOMMUNICATIONS SPACES
- 12 APPENDIX A: FULL COST OPINION



OVERVIEW

The King County Secure Community Transition Facility (SCTF), established in 2006, is a state-operated facility under the administration of the Special Commitment Center (SCC) within the Behavioral Health Administration (BHA) of the Department of Social and Health Services (DSHS). The SCTF is designed to provide a secure environment with strictly controlled access and monitored movement, ensuring safety and security while offering treatment programs.

Hargis Engineers was retained to provide an assessment of the current Information Technology Network Infrastructure and develop recommendations for network improvements. The objective of the assessment was to review and evaluate the current campus backbone distribution system, the condition of horizontal cabling, telecommunications grounding, existing physical media types, physical pathways, physical spaces, and supporting electrical and mechanical systems and compare the existing conditions to current industry standards specific to this

CONSULTING TEAM

Hargis Engineers, Inc. Seattle, WA 98101

Patrick Shannon, RCDD, PMP

Principal

Ben Helms, PE, RCDD Associate



facility type. Excluded from the assessment were electronic systems, applications, and hardware, such as the network switches and servers.

The existing campus telecommunications cabling infrastructure includes intra-building optical fiber cabling. The existing backbone cabling was installed in 2019 as part of the facility's expansion. While the backbone fiber cabling is still in good physical condition, it does not conform with current TIA industry standards for healthcare facilities.

The existing horizontal cabling within the building includes unshielded twisted-pair copper to provide connectivity to computers, telephones, printers, and other network attached devices. The condition of the cabling varies, with roughly half being Category 5e and half consisting of Category 6, which does not meet current industry infrastructure standards. Based on physical inspection and review of existing documentation, it is determined that the existing IT infrastructure does not comply with most of the current industry standards and will not support evolutions to modern and/or future technologies.

The existing optical fiber infrastructure, consisting of OM3 50-micron multi-mode optical fiber cable, is antiquated and is unable to support the deployment of new technologies. Improving the IP backbone connectivity will be a fundamental component to creating an environment that will permit King County SCTF and DSHS to identify, adapt, and implement new technologies that contribute to safety and operational improvements. New single and multi-mode optical fiber cabling will be required to provide the required backbone capacity.

OBJECTIVES

The project objectives are as follows:

- Inventory and document the condition of the existing telecommunications infrastructure, including telecommunications spaces, pathways, backbone, and cabling.
- » Identify current deficiencies.
- Recommend infrastructure improvements to bring the campus infrastructure into compliance with current codes and standards.
- Provide As-built drawings, documenting current conditions.
- » Provide a ROM cost opinion for infrastructure improvements.



CABLING INFRASTRUCTURE CODE COMPLIANCE



ΗΛRGIS



PROJECT APPROACH & STANDARDS



PROJECT APPROACH

Hargis conducted a site visit to review existing conditions including:

- » Type of backbone cabling
- » Overall architecture of backbone connectivity
- » Supporting spaces and systems, including interior and exterior pathways and spaces (telecommunications vaults and rooms)
- » Quantity, age, vintage, and condition of the horizontal cabling in each building.

The site review was limited by accessibility. Only what could be seen from plain view was evaluated, the team did not move furniture to look behind, and ceiling access was limited to minimize impact to the facility. Where cabling disappeared in walls and pathways, a certain level of deduction was used to determine the termination point, for example, we can assume that cabling for voice ports terminate at the voice cross connect on their respective floor.

As part of the assessment, the team recorded the existing conditions and the locations of voice and data ports for the purpose of creating asbuilt documentation. The as-builts include floor plans, enlarged telecom room plans, telecom rack elevations, and a backbone cabling one-line diagram.

PROJECT APPROACH



Review, assess and evaluate systems in each building



Identify the capabilities, deficiencies and vulnerabilities of each system



Provide recommendations for capital improvements to introduce, enhance, expand, or replace security system components as necessary



Develop a rough

improvement

order of magnitude

for the recommended

Chart a migration path to optimize capital investments

The team sought input from the stakeholder team and consulted current industry standards and best practices. Results from the assessment were analyzed and evaluated and a set of recommendations were developed to aid King County SCTF and DSHS stakeholders in planning future network improvement projects, budget requests, and establishing priorities. Those recommendations were analyzed to determine a possible project sequence for constructability while limiting downtime for the facility, understanding that the facility will need to remain in operation during any project.

STANDARDS & CODES

- » TIA-1179-A Healthcare Facility Telecommunications Infrastructure Standard
- » TIA-5017 Telecommunications Physical Network Security Standard
- » TIA-569 Telecommunications Pathways and Spaces
- » BICSI Telecommunications Distribution Methods Manual, 14th Edition
- » Health Insurance Portability and Accountability Act (HIPAA)

ABBREVIATIONS & GLOSSARY

BEP Building Entrance Protection

Surge protective device used to mitigate risk of damage to equipment from conductive cabling exiting the building envelope.

BICSI Building Industry Consulting Service International

BICSI is a professional association supporting the advancement of information and communications technology (ICT) profession. They publish the Telecommunications Distribution Methods Manual (TDMM) and other Telecommunications standards.

EF Entrance Facility

An environmentally controlled centralized space for telecommunications equipment that usually houses a main or intermediate cross-connect. (TIA)

ER Equipment Room

A room in a building where public and private network services can enter the building and be consolidated.

HC Horizontal Cross-Connect

A cross-connect of horizontal cabling to other cabling, e.g., horizontal or backbone equipment.

IC Intermediate Cross-Connect

A cross-connect between first-level and second-level backbone cabling. This secondary cross-connect in the backbone cabling is used to mechanically terminate and administer backbone cabling between the main cross-connect and horizontal cross-connect (station cables).

IDF Intermediate Distribution Facility

Legacy term (no longer used) for what is now defined as the TR-HC or TR-IC

IP Internet Protocol

A standard addressing scheme and message routing protocol for communication between nodes of a data network.

ISP Internet Service Provider

A company that provides subscribers with access to the internet.

IT Information Technology

Use of any computers, storage, networking, and other physical devices, infrastructure, and processes to create, process, store, secure, and exchange all forms of electronic data.

LAN Local Area Network

Collection of devices connected together in one physical location, such as a building, office, or home. A LAN can be small or large, ranging from a home network with one user to an enterprise network with thousands of users and devices in an office or school.

MC Main Cross-Connect

The centralized portion of the backbone cabling used to mechanically terminate and administer the backbone cabling; this provides connectivity between equipment rooms, entrance facilities, horizontal cross-connects and intermediate cross-connects.

MDF Main Distribution Frame

Legacy term (no longer used) for what is now defined as the TR-MC and/or TR-MER

MER Main Equipment Room

Acts as the main IT location for a building. It is the transition point for all the voice and data cabling that enters the building, and we connect it further to the other equipment rooms.

MM Multi-mode

Type of optical fiber designed to carry multiple light rays or modes simultaneously, each at a marginally different reflection angle inside the optical fiber core.

OFC Optical Fiber Cable

An optical fiber cable is a type of cable that has a number of optical fibers bundled together, which are normally covered in their individual protective plastic covers. Optical cables are used to transfer digital data signals in the form of light up to distances of hundreds of miles with higher throughput rates than those achievable via electrical communication cables. All optical fibers use a core of hair-like transparent silicon covered with less refractive indexed cladding to avoid light leakage to the surroundings. Due to the extreme sensitivity of the optical fiber, it is normally covered with a high-strength, lightweight protective material like Kevlar.

OMX Optical Mode

(X represents the multi-mode fiber classification)

Optical Fiber Classification identifying the fiber type, core size, and properties for multi-mode optical fiber. Currently, OM1-5 are on the market. See Table 1 for more information.

OSX Optical Single-mode

(X represents the fiber construction)

Optical Fiber Classification identifying the fiber type and properties for single-mode optical fiber. Currently, OS1 and 2 are on the market. See Table 1 for more information.

OSP Outside Plant Cabling

Outside plant refers to all of the physical cablings and supporting infrastructure (such as conduit, cabinets, towers, or poles), as well as any associated hardware, placed between a demarcation point in one switching facility and another switching center or customer premises.

RMFC Rack Mount Fiber Cabinet

Also know as an LIU or Fiber Patch Panel. Enclosure mounted in a network rack to allow optical fiber to be terminated and cross-connected.

SM Single-mode

Common type of optical fiber that is used to transmit over longer distances. A single-mode fiber is a single glass fiber strand used to transmit a single mode or ray of light.

TIA Telecommunications Industry Association

Professional organization providing industry standards, professional certifications, and product standards to further the information communications technology industry.

TR Telecommunications Room (previously known as IDF)

An enclosed architectural space designed to contain telecommunications equipment, cable terminations, or crossconnect cabling.

VoIP Voice over IP

A technique that allows voice to be carried in a portion of the bandwidth of an Ethernet signal that is carrying IP traffic.

WAP Wireless Access Point

» A wireless access point (WAP) is a hardware device or configured node on a local area network (LAN) that allows wireless capable devices and wired networks to connect through a wireless standard, including Wi-Fi or Bluetooth. WAPs feature radio transmitters and antennae, which facilitate connectivity between devices and the Internet or a network.

» A WAP is also known as a hotspot.

		SEQUENCING & RECOMMENDATIONS	
Phase	Prerequisites	Scope	ROM Cost Opinion
PHYSIC	AL CONSTRUC	TION OF NEW TELECOMMUNICATIONS	
1	N/A	 Retrofit Telecommunications Rooms 145 & 206 Demolish any obsolete or non-operational existing equipment to make space. Provide Electrical Infrastructure (Grounding, UPS, Convenience Receptacles, Equipment Receptacles, Power Distribution Units [PDUs]) Provide a dedicated 3-ton ductless split system cooling unit in the MDF and dedicated 1-ton ductless split system cooling unit for TRs. Expand existing Access Control, add card reader and electrically locking hardware. Install Supporting Equipment (Patch Panels, Cable Management, Rack Mount Fiber Cabinets (RMFC), Adaptor plates, Ladder Rack, etc.) 	\$74,860
INSTAL	L BACKBONE C	OFC TO NEW TELECOM SPACES	
2	N/A	 Pull 12 strand OS2 and 12 st OM4 OFC from first floor Main Equipment Room 145 to Telecommunications Room 206. Terminate OFC Cabling if RMFC is installed. 	\$1,850
INSTAL	L HORISONTAL	CABLING TO NEW TELECOMMUNICATIONS OUTLETS	
3	1	 » Install Back boxes and pathway at new telecommunications outlet locations Existing jacks will need to be maintained in operation. » Install Category 6A cabling and terminate for new telecommunications outlets. 	\$21,740
OWNER	COORDINATIO	DN REQUIRED	
4	1-3	 » Install new Ethernet Switches » Install Patch cables for active ports. » Cut over Existing workstations to the new infrastructure to allow demolition of existing telecommunications outlets. » Deploy system on new telecommunications infrastructure. 	By Owner
INSTAL	L HORIZONTAL	CABLING TO EXISTING TELECOMMUNICATIONS OUTLETS	
5	1-4	 » Install Category 6A using existing pathway to existing telecommunications outlets and terminate. - Demolish existing horizontal cabling to existing telecommunications outlets. 	\$77,300
DEMOL	ISH DEFUNCT	INFRASTRUCTURE	
6	1-5	» Demolish Existing backbone cabling - Demolish OM3 Multi-mode OFC between MER and defunct TRs.	\$7,720



BACKBONE CABLING

Service Provider Connections

King County SCTF receives internet service through a point-to-point (P2P) wireless microwave connection from an internet service provider called StarTouch Inc. The microwave connection is a wireless connection between two transceivers that creates a direct dedicated link for data transmission. Phone service provider connection is provided with a 100-pair twisted-pair copper backbone cable from the utility to the demarcation point in the first floor Equipment Room.

INTRA-BUILDING BACKBONE CABLING

12-strand OM3 50-micron multi-mode optical fiber cable is utilized between the first floor Equipment Room and second floor telecom room. To meet TIA standards, the backbone fiber cabling should be upgraded to a minimum of OM4 multi-mode and augmented with the addition of single-mode optical fiber cable. Providing 12-strand OS2 single-mode and 12-strand OM4 multi-mode optical fiber cables will provide an optical fiber backbone that is compliant with current industry standards.

HORIZONTAL CABLING

CATEGORY CABLE COMPARISON										
Category	Max. Data Rate	Bandwidth	Max. Distance	Usage						
Category 1	1 Mbps	0.4 MHz		Telephone and modem lines						
Category 2	4 Mbps	4 MHz		LocalTalk & Telephone						
Category 3	10 Mbps	16 MHz	100 m (328 ft.)	Telephone & 10BaseT Ethernet						
Category 4	16 Mbps	20 MHz	100 m (328 ft.)	Token Ring						
Category 5	100 Mbps	100 MHz	100 m (328 ft.)	100BaseT Ethernet						
Category 5e	1 Gbps	100 MHz	100 m (328 ft.)	100BaseT Ethernet, Residential Homes						
Category 6	1 Gbps	250 MHz	100 m (328 ft.) 10 Gb at 37 m (121 ft.)	Gigabit Ethernet, Commercial Buildings						
Category 6A	10 Gbps	500 MHz	100 m (328 ft.)	Gigabit Ethernet in Data Centers & Commercial Buildings						
Category 7	10 Gbps	600 MHz	100 m (328 ft.)	10 Gbps Core Infrastructure						
Category 7A	10 Gbps	1000 MHz	100 m (328 ft.) 40 Gb at 50 m (164 ft.)	10 Gbps Core Infrastructure						
Category 8	25 Gbps (Cat8.1) 40 Gbps (Cat8.2)	2000 MHz	30 m (98ft.)	25 Gbps/40 Gbps Core Infrastructure						

Source: https://tripplite.eaton.com/products/ethernet-cable-types



VOICE HORIZONTAL CABLING

Upon review of the voice infrastructure at King County SCTF, it has been identified as insufficient to meet the current and future communication needs. The existing phone system uses a VOIP system based on Category 5e and 6 cabling, which is patched to a VOIP switch.

The existing Category 5e and 6 infrastructure is not adequate to meet the current and future needs of King County SCTF. The Category 5e and 6 cabling are not in compliance with TIA standards for infrastructure. It is recommended that the existing cabling infrastructure be replaced with new cabling infrastructure, and the voice network be collapsed onto a converged network infrastructure utilizing standards compliant Category 6A cabling.

ETHERNET HORIZONTAL CABLING

The existing ethernet network is comprised of a mix of Category 5e and 6 cabling. The existing patch panels, connectors, and patch panels meet Category 5e and 6 standards. King County SCTF underwent a project to install wireless access point cabling in the second-floor office space, but the wireless access point devices were never installed.

MICROSOFT TEAMS BANDWIDTH REQUIREMENTS PER ENDPOINT											
	MINI	мим	RECOM	MENDED	BEST PERFORMANCI						
	Download	Upload	Download	Upload	Download	Upload					
AUDIO											
One-to-One	10 kbps	10 kbps	58 kbps	58 kbps	76 kbps	76 kbps					
Meetings	10 kbps	10 kbps	58 kbps	8 kbps 58 kbps 76 kbps		76 kbps					
VIDEO											
One-to-One	150 kbps	150 kbps	1.5 Mbps	1.5 Mbps	4 Mbps	4 Mbps					
Meetings	150 kbps	200 kbps	2.5 Mbps	4 Mbps	4 Mbps	4 Mbps					
SCREEN SHA	RING										
One-to-One	200 kbps	200 kbps	1.5 Mbps	1.5 Mbps	4 Mbps	4 Mbps					
Meetings	250 kbps	250 kbps	2.5 Mbps	2.5 Mbps	4 Mbps	4 Mbps					
TOGETHER M	ODE										
Meetings	1 Mbps	1.5 Mbps	1.5 Mbps	2.5 Mbps	2.5 Mbps	4 Mbps					
• • • • • •											

Source: https://learn.microsoft.com/en-us/microsoftteams/prepare-network

Category 6 cabling was installed to support the wireless infrastructure.

The existing Category 5e and 6 infrastructure is not adequate to meet the current and future needs of King County SCTF. The Category 5e and 6 cabling are not in compliance with TIA standards for infrastructure. It is recommended that the existing cabling infrastructure be replaced with a new Category 6A cabling infrastructure. Meeting TIA-1179-A standards will require the entire channel to be Category 6A certified. Meeting this requirement will require all new patch panels, modular jacks, and wall outlets comprising a replacement of the entire infrastructure. Existing Category 5e and Category 6 patch panels will be removed in favor of the Category 6A infrastructure. See sequencing and recommendations for sequencing of the project to minimize down time while the infrastructure is replaced.

TELECOMMUNICATIONS SPACES

The existing telecommunications spaces are not compliant with current standards. Inconsistent grounding was observed during the walkthrough, increasing the risk of damage to equipment from transient voltages.

To support future expanded infrastructure and meet industry standards, it is recommended to modify the telecommunications rooms. Category 6A patch panels will have to be provided and network support equipment will have to be grounded to their bonding busbar. To comply with the Health Insurance Portability and Accountability Act (HIPAA) and meet telecommunications standards, access to the space will need to be provided to limit access to authorized staff. Access control can be accomplished using different methods, including, keys and locks or an electronic access control system. Per HIPAA security requirements, the entity must "Implement procedures to control and validate a person's access to facilities based on their role or function..." Electronic access control systems have this capability built in. This capability can be accomplished for keys and locks through the use of third-party key control systems like Keywatcher or other manual processes of controlling the physical keys, which allows keys to be checked out after entering a code or some other means of identifying information to validate a person's access to the telecommunications spaces. See room summaries later in this document.

EVALUATIO	DN	CRITERIA FOR TELECOMMUNICATIONS ROOMS
Room/Space	»	Quantity, Location, and Size of Telecommunications Room.
	»	Available space to install and terminate new cabling and rack space to mount new equipment
	»	Adequate working clearances to access and maintain additional equipment and cabling
	»	Space is dedicated to telecommunications
	»	Space is secured to prevent unauthorized access.
Racks	»	Equipment racks with available space for new rack mounted network equipment required to support programs housed in building or area
Grounding &	»	Grounding bus bar bonded to NEC recognized grounding systems
Bonding	»	Equipment and cabling bonded to ground
UPS	»	Uninterruptable Power Supply (UPS) in place and operational to provide backup power in case of power failure
	»	UPS sized to provide adequate run time to support new network equipment
Cooling	»	Dedicated cooling equipment for equipment housed in space
	»	Expected life span of existing equipment
	»	Adequate capacity to support new equipment
Backbone Cabling	»	Existing fiber backbone with bandwidth and capacity to support current and future applications
	»	Minimum of 12 single-mode and 12 multi-mode optical fiber cables.
Cable	»	Cable trays and wall mounted support systems
Management	»	Rack-mounted vertical and horizontal cable management systems
Pathway	»	Dedicated telecommunications standard compliant pathways
	»	Spare conduits available with capacity for new cabling

HARGIS

MAIN EQUIPMENT ROOM

EQUIPMENT ROOM 145

The Main Equipment Room is on the first floor. One wall of the room supports the voice horizontal cabling terminations and patching. There is a mix of current and abandoned cabling, building entrance protection, and termination blocks. There is a wall-mounted rack housing fiber patch panels for a 12-strand OM3 multi-mode OFC. It also houses a 24-port and a 48-port Category 5e patch panel. The room is served by a 12-strand OM3 multi-mode OFC to the upper telecom room and a 100-pair Category 3 twisted-pair copper cable from the Service Provider. There is currently no room for expansion due to the limited sizing of the space. A grounding bus bar has been installed in the room, but there is no proper bonding to the telecom equipment. There is cooling and humidity control present in the room. There are a few convenience receptacles but no dedicated equipment receptacles. UPS power is available to provide clean, uninterrupted power for the equipment. The room can be locked but there is no other access control on the room.

It is recommended to bond telecom equipment to the grounding bus bar to create a consistent potential across all components. A new standardscompliant backbone and horizontal cabling are recommended. The addition of card-based access control or other measures is recommended to control and track access to the space.

STANDARDS COMPLIANCE COMPLIANT NON-COMPLIANT



Deficiencies:

- » Horizontal Cabling infrastructure does not meet minimum standards per TIA-1179-A.
- » Backbone Cabling Infrastructure does not meet minimum standards per TIA-1179-A.
- » No overhead ladder tray for cable support, leading to cables being draped or placed directly on equipment.
- » Equipment is not bonded to the Telecommunications Grounding Busbar.
- » Electrical infrastructure does not meet minimum requirements per standards.
- » Uncontrolled access to space with no identity verification

Recommendations:

- » Upgrade existing port locations to Category 6A.
- » Add additional Category 6A 8P8C RJ45 ports to meet standards.
- » Provide new 12-strand OS2 single-mode and 12-strand OM4 multi-mode optical fiber backbone from second floor telecom room.
- » Add ladder tray and cable management, as needed.
- » Bond equipment to the Telecommunications Grounding Busbar.
- » Add power circuits and receptacles, as needed.
- » Control access to authorized individuals.



Abandoned 110-block





TGB & Service Entrance Copper Wall-mounted Equipment



Wall-mounted Rack

 \mathbb{A}

T T

TELECOM ROOM 206 - TR-206

The Telecom Room 206 for King County SCTF is on the second floor. This telecom room was added in 2019 as part of the facility expansion. There is a two-post equipment rack housing fiber patch panels for a 12 strand OM3 multi-mode OFC. It also houses a 48-port Category 6 patch panel. The room is served by a 12-strand OM3 multi-mode OFC to the Main Equipment Room. Room for expansion is available in the same rack space. A grounding bus bar has been installed in the room, but there is no proper bonding to the telecom equipment. There is cooling and humidity control present in the room. UPS power is available to provide clean, uninterrupted power for the equipment. The room can be locked but there is no other access control on the room.

New standards compliant backbone and horizontal cabling are recommended. The addition of card-based access control or other measure is recommended to control and track access to the space.







50MM OM3 Fiber



Grounding Busbar Not Connected to Rack

Deficiencies:

- » Horizontal Cabling infrastructure does not meet minimum standards per TIA-1179-A.
- » Backbone Cabling Infrastructure does not meet minimum standards per TIA-1179-A.
- » No overhead ladder tray for cable support, leading to cables being draped or placed directly on equipment.
- » Equipment is not bonded to the Telecommunications Grounding Busbar.
- » Electrical infrastructure does not meet minimum requirements per standards.
- » Uncontrolled access to space with no identity verification.



Telecommunications Rack

Recommendations:

- » Upgrade existing port locations to Category 6A.
- » Add additional Category 6A 8P8C RJ45 ports to meet standards.
- » Provide new 12-strand OS2 single-mode and 12-strand OM4 multi-mode optical fiber backbone from second floor telecom room.
- » Add ladder tray and cable management as needed.
- » Bond equipment to the Telecommunications Grounding Busbar.
- » Add power circuits and receptacles as needed.
- » Control access to authorized individuals.

ΗΛRGIS

APPENDIX A: FULL COST OPINIONS

seattle, washington 98101 **Telecommunications Infrastructure Assessment Recommendations** 206.448.3376 King County Secure Community Transition Facility www.hargis.biz BASIS OF OPINION Pre-Design PREPARED BY Tin Vo DATE June 11, 2024 24077 JOB NUMBER CHECKED BY Ben Helms **OVERHEAD & PROFIT** 20% telecommunications summary subtotal ОН&Р total \$ 152,890 \$ 30,578 \$ Main Building 183,468 Sub-Total \$ 152,890 \$ 30,578 \$ 183,468 General Contractor OH&P 15% \$ 27,520 \$ Escalation 7% 1,926 Ś 212,915 Total

EXCLUSIONS

1 - Design contingency

2 - Sales Tax

HARGIS

1201 third avenue, ste 600

13

Main Building

Telecommunications Infrastructure Assessment Recommendations

King County Secure Community Transition Facility

BASIS OF OPINION	Pre-Design	F	PREPARED B	Y Tin Vo				DATE	1	une 11, 2024
JOB NUMBER	24077		CHECKED B	Y Ben Helms				OVERHEAD &	PROFIT	20%
		quar	ntity	materia	l cost	labor	cost	engi	ineering opini	on
description		number	unit	unit cost	total	unit cost	total	subtotal	OH&P	total
DIVISION 27										
LOW-VOLTAGE SYSTI	EMS - DIVISIONS 27									
General Provision	ns (Submittals, Mobilization, Permits)	1	LS	2,005.71	2,006	4,011	4,011	6,017	1,203	7,221
Basic Materials ar	nd Methods	1	LS	4,199.59	4,200			4,200	840	5,040
(Consumables	s, Small Tools, Equip Rental,									
Grounding, Id	lentification, etc.)									
SECTION 271100 TEL	ECOMMUNICATION DISTRIBUTION SYSTEM									
New Telecommu	nications Rooms - MC		EA	18,000.00		5,000.00				
New Telecommu	nications Rooms - HC		EA	12,000.00		2,500.00				
New Telecommu	nications Rooms - HC		EA	4,500.00		1,200.00				
Backbone Cabling	g - Copper & Optical Fiber		LF	3.00		2.75				
Adaptor Plates - L	LC	4	EA	150.00	600	50.00	200	800	160	960
Rack Mount Fiber	r Cabinet - 4RU		EA	390.00		110.00				
Rack Mount Fiber	r Cabinet - 2RU	1	EA	300.00	300	110.00	110	410	82	492
Ladder Rack			LF	7.50		20.00				
Ventilated Rack			EA	7,500.00		800.00				
20KVA UPS		1	EA	12,600.00	12,600	110.00	110	12,710	2,542	15,252
2000VA UPS			EA	3,000.00		110.00				
Telecommunicati	on Room Demolition		EA			2,000.00				
Demolish Defunc	t Infrastructure After System Cutover	1	LS			6,000.00	6,000	6,000	1,200	7,200

HARGIS

1201 third avenue, ste 600 seattle, washington 98101 206.448.3376

www.hargis.biz

14

Main Building

Telecommunications Infrastructure Assessment Recommendations

King County Secure Community Transition Facility

BASIS OF OPINION	Pre-Design	PREPARED BY Tin Vo	DATE	June 11, 2024
JOB NUMBER	24077	CHECKED BY Ben Helms	OVERHEAD & PROFIT	20%

		quantity		material cost		cost	engineering opinion		
description	number	unit	unit cost	total	unit cost	total	subtotal	OH&P	total
12 Strand Singlemode Outside Plant (OSP) OFC		LF	2.50		.05				
12 Strand Multimode Outside Plant (OSP) OFC		LF	1.19		.05				
12 Strand Singlemode Plenum Rated OFC	100	LF	.94	94	.05	5	99	20	118
12 Strand Multimode Plenum Rated OFC	100	LF	1.25	125	.05	5	130	26	156
Telecommunications Device - 4-Port	7	EA	1,100.00	7,700	473.67	3,316	11,016	2,203	13,219
Telecommunications Device - 4-Port - Existing	29	EA	1,100.00	31,900	473.67	13,737	45,637	9,127	54,764
CAT 6A Quickport Connector	56	EA	36.16	2,025	25.00	1,400	3,425	685	4,110
CAT 6A Quickport Connector - Existing	232	EA	36.16	8,388	26.00	6,032	14,420	2,884	17,304
CAT 6A Patch Panel	3	EA	320.11	960	150.00	450	1,410	282	1,692
Copper 6-port Empty Cassette	24	EA	100.00	2,400	50.00	1,200	3,600	720	4,320
Telecom Room - Electrical Improvements	2	EA	4,000.00	8,000	2,500.00	5,000	13,000	2,600	15,600
Telecom Room - HVAC - Ductless Split System	1	EA	7,500.00	7,500	1,500.00	1,500	9,000	1,800	10,800
Pathway per Drop	7	EA	200.00	1,400	150.00	1,050	2,450	490	2,940
Subtotal Low-Voltage Systems (Divisions 27)							134 323	26 865	161 187

Subtotal Low-Voltage Systems (Divisions 27)

134,323 26,865 161,187

DIVISION 28									
LIFE SAFETY & SECURITY SYSTEMS - DIVISIONS 28									
General Provisions (Submittals, Mobilization, Permits)	1	LS	209.64	210	419.28	419	629	125.78	755
Basic Materials and Methods	1	LS	390.40	390			390	78.08	468
(Consumables, Small Tools, Equip Rental,									
Grounding, Identification, etc.)									
Raceway, Cabling Supports and Outlet Boxes	2	EA	200.00	400	200.00	400	800	160	960

HARGIS

1201 third avenue, ste 600 seattle, washington 98101 206.448.3376

www.hargis.biz

Main Building

Telecommunications Infrastructure Assessment Recommendations

King County Secure Community Transition Facility

BASIS OF OPINION	Pre-Design	PREPARED BY Tin Vo	DATE	June 11, 2024
JOB NUMBER	24077	CHECKED BY Ben Helms	OVERHEAD & PROFIT	20%

	quai	quantity		material cost		cost	engineering opinion		on
description	number	unit	unit cost	total	unit cost	total	subtotal	OH&P	total
ECTION 281300 ACCESS CONTROL SYSTEM									
Access Control Panel w/ Controller	1	EA	2,800.00	2,800	680.00	680	3,480	696	4,176
Door Controller - 2-Door	1	EA	535.00	535	85.00	85	620	124	744
Power Supply 10A/24V - 8-Door	1	EA	925.00	925	170.00	170	1,095	219	1,314
Power Supply 10A/24V - 16-Door		EA	1,950.00		255.00				
Portal Licenses	2	EA	100.00	200	50.00	100	300	60	360
Card Reader	2	EA	325.00	650	127.50	255	905	181	1,086
Electrified Hardware (Electrified Lock and Power Transfer)	2	EA	1,800.00	3,600	600.00	1,200	4,800	960	5,760
Request To Exit (REX)	2	EA	125.00	250	85.00	170	420	84	504
Wiring - Per Access Control Door	2	EA	400.00	800	700.00	1,400	2,200	440	2,640
Programming	1	LS			1,952.00	1,952	1,952	390	2,342
Engineering	1	LS			976.00	976	976	195	1,171
Subtotal Life Safety and Security Systems (Divisions 28)							18,567	3,713	22,28

www.hargis.biz

1201 third avenue, ste 600 seattle, washington 98101 206.448.3376

16